



SUPPLEMENTAL BID BULLETIN 01

January 30, 2023

SUBJECT: Bid Reference No: 2023-04 “Supply of Materials and Labor for Dry Docking and Repair of M/V DA-BFAR”

This Supplemental Bid Bulletin No. 1 is issued to all participating bidders to clarify, amend and/ or modify certain provisions and requirements set forth under the above-entitled procurement project:

Invitation to Bid

FROM/ Bidder's Inquiry	TO/ BFAR Response
Bid Reference No, 2022-60	Bid Reference No. 2023-04

Bid Data Sheet

FROM/ Bidder's Inquiry	TO/ BFAR Response
5,3 Contract Similar to the Project	5,3 Contract Similar to the Project
Golden Arrow <ul style="list-style-type: none"> - Request to replace Patrol Vessel drydocking and repair of machineries” to Patrol Vessel or Research Vessel or Power Barge or Cargo Vessel drydocking and repair of machineries 	Change to Research Vessel or Patrol Vessel/ Cargo Vessel
Colorado Shipyard <ul style="list-style-type: none"> - Research vessel or patrol vessel 	
Banares <ul style="list-style-type: none"> - Fishing vessel 	
Single contract similar to the Project within five (5) years prior to the deadline of submission	Ok, change to ten (10) years
Josefa and Colorado Shipyard change to ten (10) years	

Schedule of Requirements

FROM/ Bidder's Inquiry	TO/ BFAR Response
Colorado Shipyard: Can we change into ninety-five (95) calendar days?	No, retain within NINETY (90) calendar days from receipt of Notice to Proceed (NTP) by the winning bidder
Place of Delivery: Sangley Point, Cavite City	Place of Delivery: Navotas City Fishport

Technical Specifications

FROM/ Bidder's Inquiry	TO/ BFAR Response
<p>D. Drydocking Works</p> <p>6. Structural Repair Works Crop-out and re-plate dilapidated forecastle deck flooring, grind and smoothening surface and apply epoxy primer and paint using yard supply materials (2pcs MSP 10mm x 4ft x 8ft).</p>	<p>D. Drydocking Works</p> <p>6. Structural Repair Works Crop-out and re-plate dilapidated forecastle deck flooring, grind and smoothening (bare metal) surface and apply epoxy primer and paint using yard supply materials (2pcs MSP 10mm x 4ft x 8ft).</p>
<p>D. Drydocking Works</p> <p>10. Supply of Navigational Equipment</p> <p>Supply and install RADAR/ARPA Model FAR2837S/12, 12ft antenna, 23.1", .125-96NM, 30m antenna cable with complete accessories and integrate connection with AIS, GPS, and GYRO Compass including replacement of the old unit and its accessories.</p> <p>Golden Arrow: Upgrade model to FAR2238S</p>	<p>Retain RADAR/ARPA Model FAR2837S/12</p>
<p>E. FUEL PIPINGS MAINTENANCE AND REPAIR WORKS</p> <p>2. REFRIGERATION PIPINGS MAINTENANCE AND REPAIR WORKS Replace pipe line cooling system from suction to condensing unit to overboard discharge (2-units' Auxiliary engine</p> <ul style="list-style-type: none"> 2-inches diameter inside GI pipes, schedule 80 	<p>E. FUEL PIPINGS MAINTENANCE AND REPAIR WORKS</p> <p>2. REFRIGERATION PIPINGS MAINTENANCE AND REPAIR WORKS Replace pipe line cooling system from suction to condensing unit to overboard discharge (2-units' Auxiliary engine (Refrigeration System)</p> <p>2-inches diameter inside GI pipes, schedule 80 8 pcs GI Pipe (20ft long)</p>
<p>G. DECK MACHINERIES REPAIR AND MAINTENANCE WORKS</p> <p>FORWARD, DECK FLOORING AND CO2 ROOM REPAIR WORKS:</p> <p>Remove dilapidated flooring of main deck and replace new hard wood (kin dried, 350 pcs 2" x 6" x 10ft, yakal/ tangile) including installation of cotton and epoxy marine putty (caulking) and surface</p>	<p>G. DECK MACHINERIES REPAIR AND MAINTENANCE WORKS</p> <p>FORWARD, DECK FLOORING AND CO2 ROOM REPAIR WORKS:</p> <p>Remove dilapidated flooring of main deck and replace new hard wood (kin dried, 400 pcs 350-pcs 2" x 6" x 10ft, yakal/ tangile) including installation of cotton and epoxy</p>

smoothing, chipping and grinding to bare metal, body flooring of deck flooring, application of marine epoxy primer and asphalt, prior to the installation of hard wood using yard supply and materials.	marine putty (caulking) and surface smoothing, chipping and grinding to bare metal, body flooring of deck flooring, application of marine epoxy primer and asphalt, prior to the installation of hard wood using yard supply and materials.
H. SUPPLY OF EQUIPMENT Supply of 2-units Bench Vise clamp, 10-inches Supply of 1-unit video projector with projector screen (high resolution).	H. SUPPLY OF EQUIPMENT Supply of 2-units Bench Vise clamp, 10-inches Supply of 1-unit video projector with projector screen (high resolution). Supply 10 units of portable VHF marine transceiver walkie talkie (submersible)

****nothing follows****

All other portions of the Bidding Documents affected by these amendments shall be made to conform the same.

Amendments/inclusions/clarifications made herein shall be considered an integral part of the Bidding Documents.

The changes made in the Philippine Bidding Documents (6th Edition, July 2020) are deemed integrated in terms and conditions for this project.

For further inquiries, please coordinate/call the Bids and Awards Committee Secretariat at Tel. No. 8332-4661 or bac.eps@bfar.da.gov.ph.

Please be guided accordingly.

ORIGINAL SIGNED
ATTY. MICHAEL S. ANDAYOG
BAC Chairperson