



Republic of the Philippines
Department of Agriculture
BUREAU OF FISHERIES AND AQUATIC RESOURCES
BIDS AND AWARDS COMMITTEE OFFICE

2/F Fisheries Building Complex, BPI Compound, Brgy. Vasra, Visayas Ave., Quezon City
| www.bfar.da.gov.ph | bac.eps@bfar.da.gov.ph | 0999 886 5159

NOTICE OF AWARD

F.A ASPRER CONSTRUCTION

Sampaguita St. Phase II, Ville Subdivision
Brgy. Suizo, Tarlac City

PROJECT: Bid Reference No. 2023-59 entitled “CONSTRUCTION OF NEW FENCE, GUARD HOUSE AND REPAIR OF GATE AT BFAR LONGOS WAREHOUSE”

Dear Sir/Madame:

We are pleased to notify you that the contract of the above Project is hereby awarded to your firm as the **Single Calculated and Responsive Bidder (SCRB)** and compliant with the Technical Specifications required by the end-user at Contract Price specified in the attached summary.

You are therefore required, within **ten (10)** days from the receipt of this Notice of Award, to formally enter into a contract with us, and to submit the *Performance Security* in the form and the amount stipulated in the Instructions to Bidders.

Failure to enter into the said contract or provide the Performance Security shall constitute a sufficient ground for cancellation of this award and forfeiture of your Bid Security.

Very truly yours,

ATTY. DEMOSTHENES R. ESCOTO

Head of Procuring Entity

National Director, BFAR

ZPP

I acknowledge receipt of this Notice of Award on the date indicated below:

Signature of Bidder's Authorized Representative: _____

Name of Bidder's Authorized Representative: _____

Date: _____

December 18, 2023

NOA24070066BAC



www.bfar.da.gov.ph



/BFAR.Central

DOBAC-D-02
REV. No. 00
RBO



ANNEX TO NOTICE OF AWARD

SUMMARY OF ITEMS TO BE AWARDED TO: **F.A ASPRER CONSTRUCTION**

BID REFERENCE NO.: **2023-59**

“CONSTRUCTION OF NEW FENCE, GUARD HOUSE AND REPAIR OF GATE AT BFAR LONGOS WAREHOUSE”

PR No.	LOT NO.	DESCRIPTION	APPROVED BUDGET FOR THE CONTRACT (ABC) (PHP)	CONTRACT PRICE (PHP)
23-11-1527	1	CONSTRUCTION OF NEW FENCE, GUARD HOUSE AND REPAIR OF GATE AT BFAR LONGOS WAREHOUSE	₱ 2,075,670.47	₱ 2,042,623.00
TOTAL			₱ 2,075,670.47	₱ 2,042,623.00

SPECIFICATIONS

Item No.	Item Description	Qty	Unit
I.	MOBILIZATION/ DEMOBILIZATION	1.00	lot
II.	CONCRETE PAVEMENT, 20mm thk		
	Backfill Materials	44.20	cu.m.
	Cement, 40kg	133.00	bags
	Sand, Washed	7.50	cu.m.
	Crushed Gravel, 3/4"	15.00	cu.m.
III.	CONSTRUCTION OF NEW FENCE		
A.	Siteworks		
	Demolition of Existing Fence (CHB, Beams and Columns)	1.00	lot
	Excavation	120.70	cu.m.
	Backfill and Compaction	115.20	cu.m.
	Gravel Bedding, 50mm thk	2.00	cu.m.
	Hauling and Disposal	1.00	lot

B.	Civil and Architectural Works		
1.	Concrete Works, 21 Mpa		
	<i>Column Footing, Grade Beam, Column and Lintel Beam</i>		
	Cement, 40kg	165.00	bags
	Sand, Washed	9.00	cu.m.
	Crushed Gravel, 3/4"	18.00	cu.m.
	10mmø x 6.0m Def Bar, Grade 40	210.00	pcs.
	12mmø x 6.0m Def Bar, Grade 40	150.00	pcs.
	16mmø x 6.0m Def Bar, Grade 40	116.00	pcs.
	G.A. #16 G.I. Tiewire	38.00	kgs.
2.	Formworks and Scaffoldings		
	Ordinary Plywood, 1/2" x 4' x 8'	70.00	pcs.
	Rough Lumber, 2" x 3" x 12'	285.00	pcs.
	Miscellaneous (Nails, etc.)	1.00	lot
3.	Masonry Works (including plastering)		
	CHB, 6" thk	1,620.00	pcs.
	Cement, 40kg	135.00	bags
	Sand	14.00	cu.m.
	10mmø x 6.0m Def Bar, Grade 40	111.00	pcs.
	G.A. #16 G.I. Tiewire	6.00	kgs.
4.	Painting Works		
	Wall/Column/Lintel Beam	242.90	sq.m.
	Miscellaneous (Roller, Paint Brush, Sanding Paper, etc.)	1.00	lot
IV.	REMOVAL, REPAIR AND REINSTALLATION OF EXISTING GATE		
	Removal of Existing Gate	1.00	lot
	Repair of Existing Gate, including Painting and Reinstallation	1.00	lot
V.	PROPOSED GUARD HOUSE		
A.	Siteworks		
	Excavation	27.00	cu.m.
	Backfill and Compaction	22.50	cu.m.
	Gravel Bedding, 50mm thk	1.50	cu.m.
B.	Civil and Architectural Works		
1.	Concrete Works, 21 Mpa		
	<i>Column Footing, Grade Beam, Column, Slab on Grade, Roof Beam and Carcass for Countertop</i>		
	Cement, 40kg	65.00	bags
	Sand, Washed	4.00	cu.m.
	Crushed Gravel, 3/4"	8.00	cu.m.
	10mmø x 6.0m Def Bar, Grade 40	100.00	pcs.
	12mmø x 6.0m Def Bar, Grade 40	19.00	pcs.

	16mm \varnothing x 6.0m Def Bar, Grade 40	36.00	pcs.
	G.A. #16 G.I. Tiewire	12.00	kgs.
2.	Formworks and Scaffoldings		
	Ordinary Plywood , 1/2" x 4' x 8'	18.00	pcs.
	Rough Lumber, 2" x 3" x 12'	155.00	pcs.
	Assorted Common Wire Nails	30.00	kgs.
3.	Masonry Works (including plastering)		
	CHB, 4" thk	695.00	pcs.
	Cement, 40kg	38.00	bags
	Sand	4.00	cu.m.
	10mm \varnothing x 6.0m Def Bar, Grade 40	42.00	pcs.
	G.A. #16 G.I. Tiewire	2.00	kgs.
4.	Roofing Works		
	<i>Truss</i>		
	Tubular Bar, 2" x 4" x 6mm thk x 6m	2.00	pcs.
	C-Purlins, 75mm x 35mm x 3mm thk x 6m	6.00	pcs.
	Primer Red Oxide Paint	3.00	ltrs
	Miscellaneous (Welding Rod, Paint Brush, etc)	1.00	lot
	<i>Roofing and Accessories</i>		
	Pre-Painted Long Span Rib-Type Roofing, 0.50mm thk	25.00	l.m.
	Stainless Gutter, 0.4mm x 0.61m x 2.44m	4.00	pcs.
	End Flashing, 0.4mm x 457mm x 2.44m	6.00	pcs.
	Miscellaneous (Tekscrew, Blind Rivets, Screw Bit, etc.)	1.00	lot
5.	Tileworks		
a.	Floor Tiles		
	Ceramic Floor Tiles, 60 x 60cm (for Guard's Room)	22.00	pcs.
	Ceramic Floor Tiles, 30 x 30cm (for toilet, including countertop)	45.00	pcs.
	Cement, 40kg	4.00	bags
	Sand	0.50	cu.m.
	Tile Adhesive, 25kg	3.00	bags
	Tile Grout, 2kg	2.00	bags
b.	Wall Tiles		
	Ceramic Wall Tiles, 30 x 30cm	165.00	pcs.
	Cement, 40kg	5.00	bags
	Sand	1.00	cu.m.
	Tile Adhesive, 25kg	4.00	bags
	Tile Grout, 2kg	2.00	bags
6.	Ceiling Works (including Roof Eaves)		
	Gypsum Board, 6mm thk x 4' x 8'	7.00	pcs.
	Wall Angle, 25mm x 25mm x 3.0m	15.00	pcs.

	Carrying Channel, 12mm x 38mm x 5.0m	6.00	pcs.
	Metal Furring, 19mm x 25mm x 5.0m	8.00	pcs.
	Miscellaneous (W-Clip, Black Screw, Rivets, Hanger, etc.)	1.00	lot
7.	Painting Works		
	Interior Wall/Column/Beam	42.00	sq.m.
	Exterior Wall/Column/Beam	53.00	sq.m.
	Gypsum Board Ceiling	19.50	sq.m.
	Miscellaneous (Paint Brush, Sanding Paper, etc.)	1.00	lot
8.	Doors and Windows		
a.	Doors		
	Single Swing Panel Door with Door Jamb and Complete Accessories (800mmW x 2100mmH)	1.00	set
	PVC Type Door with Door Jamb and Complete Accessories (700mmW x 2100mmH)	1.00	set
b.	Windows		
	Sliding Window with 6mm thk Annealed Glass on Powder Coated Aluminum Frame (800mmW x 1200mmH)	1.00	set
	Awning Window with 6mm thk Annealed Glass on Powder Coated Aluminum Frame (600mmW x 600mmH)	1.00	set
C.	Plumbing Works		
a.	Sanitary Lines		
	PVC Pipe, 4"Ø x 3m	2.00	pcs.
	PVC Pipe, 2"Ø x 3m	2.00	pcs.
	Elbow 90° x 4"Ø	2.00	pcs.
	Elbow 90° x 2"Ø	4.00	pcs.
	Cleanout, 4"Ø	1.00	pc.
	Sanitary Tee, 4"Ø	1.00	pc.
	Double Sanitary Tee Reducer, 4 x 2"Ø	1.00	pc.
	P-Trap, 2"Ø	1.00	pc.
	Miscellaneous (PVC Cement, Teflon, Vulcaseal, etc.)	1.00	lot
b.	Water Lines		
	PPR Pipe, 1/2"Ø x 4m (PN10)	2.00	pcs.
	Elbow 90° x 1/2"Ø	1.00	pc.
	Elbow Adapter, 1/2"Ø	2.00	pcs.
	Tee Adapter, 1/2"Ø	2.00	pcs.
	Gate Valve, 1/2"Ø	1.00	pc.
	Miscellaneous (PVC Cement, Teflon, Vulcaseal, etc.)	1.00	lot
c.	Fixtures and Accessories		
	Water Closet with Complete Accessories	1.00	set
	Lavatory with Complete Accessories	1.00	set

	Bidet with Complete Accessories	1.00	set
	Stainless Steel Floor Drain, 2"Ø	1.00	set
	Miscellaneous (PVC Cement, Teflon, Vulcaseal, etc.)	1.00	lot
D.	Electrical Works		
	PB1, Auto- Circuit Breaker 30AT (Main), 100 AF, Single Phase, 4 Branches -1-20 AT,1-30AT in Ga. # 16 Powder Coated Paint Finish, Gray	1.00	set
	3.5 mm ² , THHN Copper Conductor	1.00	roll
	LED Tube and Box Type Set (Single Ended) 18W, 220V, Daylight	1.00	sets
	LED bulb with Ceiling Receptacle, 9W, 220V, Daylight	3.00	set
	Single Switch	1.00	set
	Three Gang Switch	1.00	set
	Duplex Convenience Outlet	2.00	set
	20mm dia. x 3.0 m. PVC Pipe	4.00	pcs.
	Junction Box	4.00	pcs.
	Utility Box	4.00	pcs.
	Electrical Tape (Big)	2.00	roll
VI.	FENCING PERMIT	1.00	lot

LOT NO.	DESCRIPTION	QUANTITY	DELIVERED, WEEKS/MONTHS
1	CONSTRUCTION OF NEW FENCE, GUARD HOUSE AND REPAIR OF GATE AT BFAR LONGOS WAREHOUSE	1 lot	Within Ninety (90) calendar days from receipt of Notice to Proceed (NTP) by the winning bidder.
Place of Delivery: BFAR Longos Warehouse, Malabon City			

*****NOTHING FOLLOWS*****