



NOTICE OF AWARD

CARESYSTEM TECHNOLOGY SOLUTION CO., INC

Door 1,2,3,4 LS Bros., BLDG., KM 5 Buhangin Road, Brgy. Buhangin
Davao City, Davao Del Sur, Philippines

Dear Sir/Madame:

Bid Reference No. 2023-61 entitled "LAYOUT, SUPPLY AND INSTALLATION OF AIR CONDITIONER UNITS FOR THE GROUND AND THIRD FLOOR OF BFAR-NCR BUILDING"

We are pleased to notify you that the contract for the above Project is hereby awarded to your firm as the **Lowest Calculated and Responsive Bidder (LCRB)** and compliant with the Technical Specifications required by the end-user at the Contract Price specified in the attached summary.

You are therefore required, within **ten (10)** days from the receipt of this Notice of Award, to formally enter into a contract with us, and to submit the *Performance Security* in the form and the amount stipulated in the Instructions to Bidders.

Failure to enter into the said contract or provide the Performance Security shall constitute a sufficient ground for cancellation of this award and forfeiture of your Bid Security.

Very truly yours,

ATTY. DEMOSTHENES R. ESCOTO
Head of Procuring Entity
Director, BFAR

I acknowledge receipt of this Notice of Award on the date indicated below:

Signature of Bidder's Authorized Representative: _____

Name of Bidder's Authorized Representative: HANUEL R. CABUCANON

Date: 12 - 27 - 2023



ANNEX TO NOTICE OF AWARD

SUMMARY OF ITEMS TO BE AWARDED TO: **CARESYSTEM TECHNOLOGY SOLUTION CO., INC**

BID REFERENCE NO.: **2023-61**

"LAYOUT, SUPPLY AND INSTALLATION OF AIR CONDITIONER UNITS FOR THE GROUND AND THIRD FLOOR OF BFAR-NCR BUILDING"

LOT NO.	PR NO.	LOT TITLE	APPROVED BUDGET FOR THE CONTRACT (ABC) (PHP)	CONTRACT PRICE (PHP)
1	23-11-1557	LAYOUT, SUPPLY AND INSTALLATION OF AIR CONDITIONER UNITS FOR THE GROUND AND THIRD FLOOR OF BFAR-NCR BUILDING	₱ 2,165,876.00	₱ 1,983,762.00

Technical Specifications		
UNIT	ITEM DESCRIPTION	QTY
	LAYOUT, SUPPLY AND INSTALLATION OF AIR CONDITIONER UNITS FOR THE GROUND FLOOR AND THIRD FLOOR OF BFAR-NCR BUILDING	
	Location: 8 Kalayaan Ave., Brgy. Mayala, Diliman, Quezon, City	
	Ground Floor Schedule of Works:	
	a. Mobilization/Demobilization	
	b. Supply and Delivery of Wall Mounted Aircondition Units	
	c. Layout and Installation of Wall Mounted Aircondition Units	
	d. Electrical Works	
	Specifications:	
lot	a. Mobilization/Demobilization	1
	b. Supply and Delivery of Wall Mounted Aircon Units	
units	1. 2.0HP Aircondition Unit	4
units	2. 1.5HP Aircondition Unit	2
units	3. 0.8HP Aircondition Unit	3
	c. Layout and Installation of Wall Mounted	

Aircondition Units		
	1. 2.0HP Aircondition Unit	
	<i>Area: PB2/1, PB2/2, PB2/7, and PB2/8</i>	
lots	Supply and Layout of Mechanical Piping and Field Wiring Installation	4
lots	Supply and Layout of Drainline with Drainpump	4
lots	Supply and Installation of Service Breaker: 20A/1P/60H (Metal Enclosure Type)	4
lots	Supply and Installation of Outdoor Bracket	4
lots	Civil and Restoration Works	4
	2. 2.0HP Aircondition Unit	
	<i>Area: PB2/5 and PB2/9</i>	
lots	Supply and Layout of Mechanical Piping and Field Wiring Installation	2
lots	Supply and Layout of Drainline with Drainpump	2
lots	Supply and Installation of Service Breaker: 15A/1P/60H (Metal Enclosure Type)	2
lots	Supply and Installation of Outdoor Bracket	2
lots	Civil and Restoration Works	2
	3. 0.8HP Aircondition Unit	
	<i>Area: PB2/3, PB 2/4, and PB2/6</i>	
lots	Supply and Layout of Mechanical Piping and Field Wiring Installation	3
lots	Supply and Layout of Drainline with Drainpump	3
lots	Supply and Installation of Service Breaker: 15A/1P/60H (Metal Enclosure Type)	3
lots	Supply and Installation of Outdoor Bracket	3
lots	Civil and Restoration Works	3
	d. Electrical Works	
roll	5.5 mm ² , THHN Copper Conductor	3
m	8.0 mm ² , THHN Copper Conductor (Ground)	40
m	22.0 mm ² , THHN Copper Conductor	120
m	50.0 mm ² , THHN Copper Conductor	12
pcs	20mm dia. X 3.0 m. PVC Pipe	30
pcs	32mm dia. X 3.0 m. PVC Pipe	14
pc	175 AT Circuit Breaker, Single Phase	1
set	PB2, Auto- Circuit Breaker 80 AT (Main), 100 AF, Single Phase, 8 Branches -7-30 AT, in Ga.#16 Powder Coated Paint Finish, Gray	1



Republic of the Philippines
 Department of Agriculture
BUREAU OF FISHERIES AND AQUATIC RESOURCES
BIDS AND AWARDS COMMITTEE OFFICE

2/F Fisheries Building Complex, BPI Compound, Brgy. Vasra, Visayas Ave., Quezon City
 | www.bfar.da.gov.ph | bac.eps@bfar.da.gov.ph | 0999 886 5159

lot	1/4" x 1/4 Square Bar Grills	1
lot	Ground Rod 5/8" x 3m	1
Third Floor Schedule of Works:		
	a. Mobilization/Demobilization	
	b. Supply and Delivery of Wall Mounted Aircondition Units	
	c. Layout and Installation of Wall Mounted Aircondition Units	
	d. Electrical Works	
Specifications:		
lot	a. Mobilization/Demobilization	1
	b. Supply and Delivery of Wall Mounted Aircon Units	
units	1. 2.5HP Aircondition Unit	4
units	2. 2.0HP Aircondition Unit	3
Aircondition Units		
	1. 2.5HP Aircondition Unit	
	<i>Area: Multifunction Area (2 units) and Office Area (2 units)</i>	
lots	Supply and Layout of Mechanical Piping and Field Wiring Installation	4
lots	Supply and Layout of Drainline with Drainpump	4
lots	Supply and Installation of Service Breaker: 20A/1P/60H (Metal Enclosure Type)	4
lots	Supply and Installation of Outdoor Bracket	4
lots	Civil and Restoration Works	4
	2. 2.0HP Aircondition Unit	
	<i>Area: Regional Fisheries Information Unit (1 unit) and Office of the Regional Director (2 units)</i>	
lots	Supply and Layout of Mechanical Piping and Field Wiring Installation	3
lots	Supply and Layout of Drainline with Drainpump	1
lots	Supply and Installation of Service Breaker: 20A/1P/60H (Metal Enclosure Type)	3
lots	Supply and Installation of Outdoor Bracket	3
lots	Civil and Restoration Works	3
d. Electrical Works		
roll	5.5 mm ² , THHN Copper Conductor	3
m	8.0 mm ² , THHN Copper Conductor (Ground)	30



Republic of the Philippines
 Department of Agriculture
BUREAU OF FISHERIES AND AQUATIC RESOURCES
BIDS AND AWARDS COMMITTEE OFFICE

2/F Fisheries Building Complex, BPI Compound, Brgy. Vasra, Visayas Ave., Quezon City
 | www.bfar.da.gov.ph | bac.eps@bfar.da.gov.ph | 0999 886 5159

m	22.0 mm2, THHN Copper Conductor	60
m	50.0 mm2, THHN Copper Conductor	8
pcs	20mm dia. X 3.0 m. PVC Pipe	30
pcs	32mm dia. X 3.0 m. EMT Pipe	10
pc	175 AT Circuit Breaker, Single Phase	1
set	PB2, Auto- Circuit Breaker 80 AT (Main), 100 AF, Single Phase, 8 Branches -7-30 AT, in Ga.# AF, Single Phase, 8 Branches -7-30 AT, in Ga.# 16 Powder Coated Paint Finish, Gray	1
lot	1/4" x 1/4 Square Bar Grills	1
pc	Ground rod 5/8" x 3m	1
	Others:	
	with warranty (5 yrs - compressor, 3 yrs - Printed Circuit Board, and 1 yr on all other parts and workmanship.	

Duration: 30 calendar days

******NOTHING FOLLOWS******